

Debris Streams

Landfills are reviewed and approved at the early stages of the project.

- **Asbestos**

- Must be taken to a lined Class III Landfill, permitted to accept asbestos

- **Chimneys**

- If not containing asbestos, will be removed with ash/debris
- If containing asbestos, must be taken to a permitted and lined Class III Landfill

- **Vehicles**

- Recycled as metal once the appropriate adjudication is completed

- **Metals**

- Taken to a metal recycling facility

- **Ash/Debris**

- This is disposed of at an approved landfill

- **Concrete**

- Recycled or transported to an approved landfill

- **Soil**

- Disposed of at an approved landfill

**Hazardous Materials – Sometimes not all hazardous materials are located and removed earlier in the process. If found during debris removal, these are set aside for DTSC to conduct a pick-up.*

Soil Sampling Confirmation (mg/kg)

	Sb	As	Ba	Be	Cd	Cr	Co
Regulatory Screening Levels	31	0.11	9,999	16	7.1	2,499	23
Background Level	0.38	4.9	210	0.44	1.1	51	14
Tv Area Cleanup Goal	31	4.9	9,999	16	7.1	2,499	23

Cu	Pb	Hg	Mo	Ni	Se	Ag	Tl	V	Zn
2,499	80	1	390	820	99	390	5	390	4,999
68	74	0.4	2.3	44	0.7	0.17	0.10	90	210
2,499	80	1.0	390	820	99	390	5.0	390	4,999

- DTSC, Office of Human Health and Ecological Risk Assessment, Note 3, June 2020 (HERO Note 3)
- CalEPA, Revised California Human Health Screening Levels (CHHSL), September 2010
- California Hazardous Waste Total Threshold Limits Concentration (TTLC), California Code of Regulations, Title 22, Chapter 11, Article 3
- U.S. EPA Regional Soil Levels (RSL)